

**Texas Department of Transportation  
Technical Provisions**

**SH 183 Managed Lanes Project**

**Attachment 4-5  
EPIC Sheets**

Notes To Designer:  
 1. Do not alter Sheet Design or Font style, size or weight - match text attributes.  
 2. If additional space is needed for a numbered section, fence and adjust sections up or down as needed for proportioning and readability but do not relocate from its relative position.  
 3. All areas should be addressed thoroughly and verify the necessary pay items are set up to support actions needed.

DISCLAIMER:  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damage resulting from its use.

**I. STORMWATER POLLUTION PREVENTION PLAN-CLEAN WATER ACT SECTION 402**

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 1122.

- Construction General Permit (CGP) requires storm water pollution prevention plan, notice of intent, and notice of termination be prepared for the proposed improvements.

No Action Required       Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000.
- Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

**II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404**

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas. No equipment is allowed in any stream channel below the Ordinary High Water Mark except on approved temporary stream crossings or drill pads.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required:      RCP 12 For Elm Fork (Within Section 408)

Required Actions: List Waters of the US Permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

PERMIT	WATERS OF THE U.S.	APPROXIMATE LOCATION
NWP 14/25	Bear Creek	Sta 4527+00 to 4530+00
NWP 14/3	Estelle Creek	Sta 155+00
NWP 14/3	Dry Creek	Sta 220+00
NWP 14/3	Delaware Creek	Sta 300+00
NWP 14/3	Unnamed Tributary 1 to Delaware Creek	Sta 320+00 to 326+00
NWP 14/3	Unnamed Tributary 2 to Delaware Creek	Sta 326+00
NWP 14/3	Unnamed Tributary 3 to Delaware Creek	Sta 337+00
NWP 14/3	Unnamed Tributary 4 to Delaware Creek	Sta 363+00
RGP 12	Elm Fork Trinity River	Sta 557+00 to 561+00

The elevation of the Ordinary High Water Marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts (or as established by the Developer).

If design changes occur to the proposed, a reassessment of potential impacts would be necessary. If impacts to potentially jurisdictional features are identified due to the Developer's methodologies or activities, the Developer would be responsible for obtaining the appropriate Section 404 permits.

REFER TO EPIC SHEET 2 OF 2 - LEFT COLUMN FOR SECTION II - CONTINUATION FOR BEST MANAGEMENT PRACTICES

**III. CULTURAL RESOURCES**

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

No Action Required       Required Action

**IV. VEGETATION RESOURCES**

Preserve native vegetation to the extent practical.

No Action Required       Required Action

Action No.

- Restore and stabilize disturbed areas as soon as the construction schedule permits. Consider temporary seeding where large areas of disturbed ground would be left bare for a considerable length of time. Seeding and replanting with TxDOT approved seeding specifications that is in compliance with Executive Order 13112 shall be done where possible.

**V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRD TREATY ACT**

No Action Required       Required Action

Action No.

- The Developer shall comply with all state and federal laws and regulations as related to state and federal listed threatened and endangered species. Prior to construction, the Developer shall review the most current state and federal threatened and endangered species lists to determine if changes to the lists have occurred since the applicable NEPA Approvals. If changes to the lists have occurred, the Developer shall reassess the potential project impacts to the listed species and/or their habitat. The Developer shall take all appropriate actions to comply with applicable state and federal regulations. If it is determined that adverse effects to listed species will occur, the Developer shall work with TxDOT to develop mitigation approaches. The Developer shall prepare any materials needed for coordination or consultation with regulatory agencies, at TxDOT's direction. TxDOT will conduct coordination or consultation with the applicable state and federal agencies for the project. The Developer shall be responsible for any mitigation requirements identified from regulatory agency coordination/consultation.
- Between October 1 and February 15, remove all inactive migratory bird nests from any structures that would be affected by the proposed project, and complete any bridge work and/or vegetation clearing. Between February 15 and October 1, the Developer would be prepared to prevent migratory birds from building nests. In the event that migratory birds are encountered on-site during project construction, adverse impacts on protected birds, active nests, eggs and/or young would be avoided. If species are present, work should cease at that location and TxDOT personnel should be contacted. If any active nests are found, the local USFWS biologist should be contacted by TxDOT to determine an appropriate plan of action.

REFER TO EPIC SHEET 2 OF 2 - MIDDLE COLUMN FOR SECTION V - CONTINUATION FOR LIST OF SPECIES POTENTIALLY WITHIN PROJECT AREA WITH HABITAT DESCRIPTION AND ADDITIONAL ACTIONS

**LIST OF ABBREVIATIONS**

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	RGP: Regional General Permit
MOU: Memorandum of Understanding	TCEQ: Texas Commission on Environmental Quality
MS4: Municipal Separate Stormwater Sewer System	TPDES: Texas Pollutant Discharge Elimination System
MSDS: Material Safety Data Sheets	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	TSS: Total Suspended Solids
NOI: Notice of Intent	USACE: U.S. Army Corp of Engineers
	USFWS: U.S. Fish and Wildlife Service

**VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES**

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.

Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labeling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Developer shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer and Developer's Environmental Compliance Manager if any of the following are detected:

- Dead or distressed vegetation (not identified as normal)
- Trash piles, drums, canisters, barrels, etc.
- Undesirable smells or odors
- Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation(s) or replacement(s) (bridge class structures not including box culverts)?

Yes       No

If "No", then no further action is required.

If "Yes", then the Developer is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

Yes       No       N/A

If "Yes", then the Developer must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then the Developer is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Developer and the asbestos consultant.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

No Action Required       Required Action

Action No.

- The Developer shall comply with the recommendations of the limited Phase 1 environmental site assessment completed for the SH 183 Managed Lanes Project.
- Any unanticipated hazardous materials encountered during construction would be handled according to applicable federal, state, and local regulations per the Contract Documents. The Developer would take appropriate measures to prevent, minimize, and control the spill of hazardous materials in the construction staging area. All construction materials used for this project would be removed as soon as the work schedules permit.

**VII. OTHER ENVIRONMENTAL ISSUES**

(includes regional issues such as Trinity River Corridor Development Certificate, etc.)

REFER TO EPIC SHEET 2 OF 2 - RIGHT COLUMN FOR SECTION VII - CONTINUATION FOR LIST OF OTHER ENVIRONMENTAL ISSUES

**CONTROL-SECTION-JOB NUMBERS (CSJ'S)**

0094-03-065, 0094-07-020, 0094-07-015



**ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)**

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 183 Dallas
STATE	DIVISION	COUNTY	
TEXAS	SPD	DALLAS	SHEET NO.
CONTROL	SECTION	JOB	1 of 2

**GENERAL NOTE:**

Any change orders and/or deviations from the final design must be reported to TxDOT prior to commencement of construction activities, as additional environmental clearance may be required.

LAST REVISION: MAY 2012

Notes To Designer:

1. Do not alter Sheet Design or Font style, size or weight - match text attributes.
2. If additional space is needed for a numbered section, fence and add just sections up or down as needed for proportioning and readability but do not relocate from its relative position.
3. All areas should be addressed thoroughly and verify the necessary pay items are set up to support actions needed.

**DISCLAIMER:**

The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damage resulting from its use.

**II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404--(CONTINUATION FROM EPIC SHEET 1 OF 2)**

Best Management Practices for applicable Section 401 General Conditions:

**Erosion**

- Temporary Vegetation
- Blankets/Matting
- Mulch
- Sodding
- Interceptor Swale
- Diversion Dike
- Erosion Control Compost
- Mulch Filter Berm and Socks
- Compost Filter Berm and Socks

**Sedimentation**

- Silt Fence
- Rock Berm
- Triangular Filter Dike
- Sand Bag Berm
- Straw Bale Dike
- Brush Berms
- Erosion Control Compost
- Mulch Filter Berm and Socks
- Compost Filter Berm and Socks
- Stone Outlet Sediment Traps
- Sediment Basins

**Post-Construction TSS**

- Vegetative Filter Strips
- Retention/Irrigation Systems
- Extended Detention Basin
- Constructed Wetlands
- Wet Basin
- Erosion Control Compost
- Mulch Filter Berm and Socks
- Compost Filter Berm and Socks
- Vegetation Lined Ditches
- Sand Filter Systems

Refer also to the SW3P, project specific EPIC sheets, and Project General Notes for project specific Best Management Practices.

**V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRD TREATY ACT (CONTINUATION FROM EPIC SHEET 1 OF 2)**

Species Potentially within Project Area w/ Description

1. Alligator Snapping Turtle: Characterized by a large heavy head, and a long, thick shell with three dorsal ridges of large scales. They can be immediately distinguished from the common snapping turtle by the three distinct rows of spikes and raised plates on the carapace/shell. They are a solid gray, brown, black, or olive-green in color, and often covered with algae.
2. Bald Eagle: The plumage of an adult Bald Eagle is evenly dark brown with a white head and tail. The tail is moderately long and slightly wedge-shaped. The beak and feet are bright yellow. The legs are feather-free, and the toes are short and powerful with large talons. The plumage of the immature bald eagle is a dark brown overlaid with messy white streaking until the fifth year.
3. Timber/Canebrake Rattlesnake: Timber rattlesnakes have wide heads and narrow necks (typical distinction of all venomous snakes except coral snakes *Micrurus fulvius*). Timber rattlers are the second largest venomous snake in Texas and third largest in the United States. Adult timber rattlesnakes reach a length of 36 to 40 inches (91 to 101 cm), and weigh 1.3 to 2 pounds (0.58 to 0.9 kg). They have a heavy, light yellow, gray or greenish-white body with a rust-colored strip along the length of their back and a black tail tip tipped with rattles. Timber rattlesnakes have yellow eyes with elliptical or cat-like pupils. Twenty to 29 dark, V-shaped crossbars with jagged edges form a distinctive pattern across their back.
4. Mussels (Louisiana pigtoe, Texas heelsplitter): Adults can range from approximately 1-inch to 12-inches in length. Some species have thin shells and shells vary both on the inside and outside of mussels, depending on species. Color, texture and shape variations in shells are used to help identify types of mussels.

Habitat Description

- Perennial water bodies: deep water of rivers, canals, lakes, and oxbows; also swamps, bayous, and ponds near deep running water; sometimes enters brackish coastal waters; usually in water with mud bottom and abundant aquatic vegetation; may migrate several miles along rivers; active March-October; breeds April-October.
- Found primarily near rivers and large lakes; nests in tall trees or on cliffs near water; communally roosts, especially in winter; hunts live prey, scavenges, and pirates food from other birds.
- Swamps, floodplains, upland pine and deciduous woodlands, riparian zones, abandoned farmland; limestone bluffs; sandy soil or black clay; prefers dense ground cover, i.e. grapevines or palmetto.
- Small and large rivers especially on sand, mud, rocky mud and sand and gravel, also still to swiftly flowing waters.

Species of Concern - additional description of species and habitat information can be found in NEPA documents.

- |                           |  |
|---------------------------|--|
| 1. Western Burrowing Owl: | 4. Plains Spotted Skunk:                             |
| 2. Black Landiton Beetle: | 5. Texas Garter Snake:                               |
| 3. Cave Myotis Bat:       | 6. Fawcett, Little Spectaclecase, and Wabash Pigtoe: |

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

*Special Note: The Migratory Bird Treaty Act of 1918 states that it is unlawful to kill, capture, collect, possess, buy, sell, trade or transport any migratory bird, nest, young, feather or egg in part or in whole, without a federal permit issued in accordance with the Act's policies and regulations. The Developer would remove all inactive migratory bird nests from any structures where work would be done from October 1 to February 15. In addition, the Developer would be prepared to prevent migratory birds from building nest(s) between February 15 to October 1. In the event that migratory birds are encountered on-site during project construction, effort to avoid adverse impacts on protected birds, active nests, eggs and/or young would be required.*

**LIST OF ABBREVIATIONS**

- |   |   |
|---|---|
| BMP: Best Management Practice                   | SPCC: Spill Prevention Control and Countermeasure   |
| CGP: Construction General Permit                | SW3P: Storm Water Pollution Prevention Plan         |
| DSHS: Texas Department of State Health Services | PCN: Pre-Construction Notification                  |
| FHWA: Federal Highway Administration            | PSL: Project Specific Location                      |
| MOA: Memorandum of Agreement                    | TCEQ: Texas Commission on Environmental Quality     |
| MOU: Memorandum of Understanding                | TPDES: Texas Pollutant Discharge Elimination System |
| MS4: Municipal Separate Stormwater Sewer System | TPWD: Texas Parks and Wildlife Department           |
| MSDS: Material Safety Data Sheets               | TxDOT: Texas Department of Transportation           |
| MBTA: Migratory Bird Treaty Act                 | T&E: Threatened and Endangered Species              |
| NOT: Notice of Termination                      | TSS: Total Suspended Solids                         |
| NWP: Nationwide Permit                          | USACE: U.S. Army Corps of Engineers                 |
| NOI: Notice of Intent                           | USFWS: U.S. Fish and Wildlife Service               |

**VII. OTHER ENVIRONMENTAL ISSUES (CONTINUATION FROM EPIC SHEET 1 OF 2)**  
(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required
- Required Action


1. **Water Quality** Runoff from this project discharges within 5 stream miles upstream of Segment 0841 of the lower West Fork of the Trinity River basin which is listed as threatened/impaired for PCB's, dioxins, and fecal coliform bacteria in edible tissue on the Texas 2012 303(d) list. Select appropriate BMP's to control the constituent of concern at this location.
2. **MS4 Requirements** The proposed project is located within the boundaries of the Cities of Fort Worth, Irving, and Dallas and TxDOT's municipal separate storm sewer system (MS4) Phase I and Euless Phase II permits. Compliance with the applicable MS4 permit(s) is required.
3. **Trinity River Corridor** Portions of the project cross the Trinity River Corridor; therefore a Corridor Development Certificate (CDC) is required. The Developer is responsible to coordinate and obtain the CDC.
4. **Floodplains** Hydraulic design to be in accordance with TxDOT and FHWA design policy procedures. The proposed improvements would permit the conveyance of the design year flood, inundation of the roadway being acceptable, without causing substantial damage to the highway, stream or other property. The proposed project must not increase the base flood elevation to a level that would violate applicable floodplain regulations and ordinances.
5. **Construction Air Quality** Incorporate measures to control fugitive dust during construction such as covering or treating disturbed areas with dust suppression techniques, sprinkling, covering loaded trucks and other dust abatement controls as appropriate.
6. **Construction Emissions Reduction Plan** The Texas Emissions Reduction Plan (TERP) includes incentive programs to encourage the development of multi-pollutant approaches to ensure that the air in Texas is both safe to breathe and meets minimum federal standards. TxDOT encourages Developers to utilize the TERP program to the fullest extent possible to minimize diesel emissions. Information about the TERP program can be found at <http://www.tceq.state.us/implementation/air/terp/>.
7. **Construction Impacts** Developer to make every reasonable effort to minimize construction noise through abatement measures such as work-hour controls (i.e., minimization of nighttime construction at residential areas) and proper maintenance of muffler systems. Notify city and local safety officials of proposed road closures or detours. Detour timing and necessary rerouting of emergency vehicles would be coordinated with the proper local officials. Lane closures and detours are to comply with TxDOT requirements and the Manual of Uniform Traffic Control Devices.
8. **Visual Resources/Aesthetics** TxDOT has begun discussions with local jurisdictions regarding aesthetic features. The Developer shall adhere to the aesthetic requirements.
9. **Threatened and Endangered Species** Developer shall conduct mussel surveys prior to construction.
10. **Habitat Mitigation** 7.75 acres of unusual habitat vegetation would be mitigated on tracts at Lewisville Lake Environmental Learning Center.
11. **Noise** The wall at the O'Connor Road overpass would be constructed as part of the interim SH 183 project. The constructed barrier along the eastbound frontage road lanes between Wm. Brewster and West Park would be extended approximately 100 feet.
12. **Section 408** Developer shall be responsible for obtaining construction approval from the USACE.

**GENERAL NOTE:**

Any change orders and/or deviations from the final design must be reported to TxDOT prior to commencement of construction activities, as additional environmental clearance may be required.

*This document is released for information purposes and is subject to change based on comments from approving agencies and public input. It is not to be used for construction purposes.*

LAST REVISION: MAY 2012

CONTROL-SECTION-JOB NUMBERS (CSJ'S)			
0094-03-065, 0094-07-020, 0094-07-015			
 Texas Department of Transportation Dallas District Standard			
<b>ENVIRONMENTAL PERMITS,          ISSUES AND COMMITMENTS          (EPIC)</b>			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 183 Dallas
STATE	DIVISION	COUNTY	
TEXAS	SPD	DALLAS	SHEET NO.
CONTROL	SECTION	JOB	2 of 2

DISCLAIMER:  
 The use of this standard is governed by the "Texas Engineering Practice Act".  
 No warranty of any kind is made by TxDOT for any purpose whatsoever.  
 TxDOT assumes no responsibility for the conversion of this standard to other  
 formats or for incorrect results or damage resulting from its use.

Notes To Designer:  
 1. Do not alter Sheet Design or Font style, size or weight - match text attributes.  
 2. If additional space is needed, for a numbered section fence and add just sections up or down  
 as needed for proportioning and readability but do not relocate from its relative position.  
 3. All areas should be addressed thoroughly and verify the necessary pay items are set up to  
 support actions needed.

**I. STORMWATER POLLUTION PREVENTION PLAN-CLEAN WATER ACT SECTION 402**

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 1122.

1. Construction General Permit (CGP) requires storm water pollution prevention plan, notice of intent, and notice of termination be prepared for the proposed improvements.

No Action Required       Required Action

Action No.

1. Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000.
2. Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
3. Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
4. When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

**II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404**

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas. No equipment is allowed in any stream channel below the Ordinary High Water Mark except on approved temporary stream crossings or drillpads.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required:

Required Actions: List Waters of the US Permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

PERMIT	WATERS OF THE U.S.	APPROXIMATE LOCATION
NWP 14/3	Unnamed Tributary 1 to Trinity River	SH 183 Sta 4363+00
NWP 14/3	Unnamed Tributary to Bear Creek	SH 183 Sta 4523+00 to 4528+00
NWP 14/25	Bear Creek	SH 183 Sta 4528+00 to 4530+00

The elevation of the Ordinary High Water Marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts (or as established by the Developer).

If design changes occur to the proposed, a reassessment of potential impacts would be necessary. If impacts to potentially jurisdictional features are identified due to the Developer's methodologies or activities, the Developer would be responsible for obtaining the appropriate Section 404 permits.

REFER TO EPIC SHEET 2 OF 2 - LEFT COLUMN FOR SECTION II - CONTINUATION FOR BEST MANAGEMENT PRACTICES

**III. CULTURAL RESOURCES**

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

No Action Required       Required Action

**IV. VEGETATION RESOURCES**

Preserve native vegetation to the extent practical.

No Action Required       Required Action

Action No.

1. Restore and stabilize disturbed areas as soon as the construction schedule permits. Consider temporary seeding where large areas of disturbed ground would be left bare for a considerable length of time. Seeding and replanting with TxDOT approved seeding specifications that is in compliance with Executive Order 13112 shall be done where possible.

**V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRD TREATY ACT**

No Action Required       Required Action

Action No.

1. The Developer shall comply with all state and federal laws and regulations as related to state and federal listed threatened and endangered species. Prior to construction, the Developer shall review the most current state and federal threatened and endangered species lists to determine if changes to the lists have occurred since the applicable NEPA Approvals. If changes to the lists have occurred, the Developer shall reassess the potential project impacts to the listed species and/or their habitat. The Developer shall take all appropriate actions to comply with applicable state and federal regulations. If it is determined that adverse effects to listed species will occur, the Developer shall work with TxDOT to develop mitigation approaches. The Developer shall prepare any materials needed for coordination or consultation with regulatory agencies, at TxDOT's direction. TxDOT will conduct coordination or consultation with the applicable state and federal agencies for the project. The Developer shall be responsible for any mitigation requirements identified from regulatory agency coordination/consultation.
2. Between October 1 and February 15, remove all inactive migratory bird nests from any structures that would be affected by the proposed project, and complete any bridge work and/or vegetation clearing. Between February 15 and October 1, the Developer would be prepared to prevent migratory birds from building nests. In the event that migratory birds are encountered on-site during project construction, adverse impacts on protected birds, active nests, eggs and/or young would be avoided. If species are present, work should cease at that location and TxDOT personnel should be contacted. If any active nests are found, the local USFWS biologist should be contacted by TxDOT to determine an appropriate plan of action.

REFER TO EPIC SHEET 2 OF 2 - MIDDLE COLUMN FOR SECTION V - CONTINUATION FOR LIST OF SPECIES POTENTIALLY WITHIN PROJECT AREA WITH HABITAT DESCRIPTION AND ADDITIONAL ACTIONS

**LIST OF ABBREVIATIONS**

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MSDS: Material Safety Data Sheets	TxDOT: Texas Department of Transportation
MBTA: Migratory Bird Treaty Act	T&E: Threatened and Endangered Species
NOT: Notice of Termination	TSS: Total Suspended Solids
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

**VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES**

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.

Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labeling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Developer shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer and the Developer's Environmental Compliance Manager if any of the following are detected:

- Dead or distressed vegetation (not identified as normal)
- Trash piles, drums, canisters, barrels, etc.
- Undesirable smells or odors
- Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation(s) or replacement(s) (bridge class structures not including box culverts)?

Yes       No

If "No", then no further action is required.

If "Yes", then the Developer is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

Yes       No       N/A

If "Yes", then the Developer must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then the Developer is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Developer and the asbestos consultant.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

No Action Required       Required Action


Action No.

1. The Developer shall comply with the recommendations of the limited Phase 1 environmental site assessment completed for the SH 183 Managed Lanes Project.
2. Any unanticipated hazardous materials encountered during construction would be handled according to applicable federal, state, and local regulations per the Contract Documents. The Developer would take appropriate measures to prevent, minimize, and control the spill of hazardous materials in the construction staging area. All construction materials used for this project would be removed as soon as the work schedules permit.

**VII. OTHER ENVIRONMENTAL ISSUES**

(includes regional issues such as Edwards Aquifer District, etc.)

REFER TO EPIC SHEET 2 OF 2 - RIGHT COLUMN FOR SECTION VII - CONTINUATION FOR LIST OF OTHER ENVIRONMENTAL ISSUES

CONTROL-SECTION-JOB NUMBERS (CSJ'S)			
0364-01-054, 0364-05-025, 0364-05-925, 0094-02-077, 0094-02-977			
 2012 Texas Department of Transportation Dallas District Standard			
ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 183 SEGMENT 2E
STATE	DIVISION	COUNTY	
TEXAS	SPD	TARRANT/DALLAS	
CONTROL	SECTION	JOB	
			SHEET NO. 1 of 2

**GENERAL NOTE:**

Any change orders and/or deviations from the final design must be reported to TxDOT prior to commencement of construction activities, as additional environmental clearance may be required.

LAST REVISION: MAY 2012

Notes To Designer:

1. Do not alter Sheet Design or Font style, size or weight - match text attributes.
2. If additional space is needed for a numbered section, fence and adjust sections up or down as needed for proportioning and readability but do not relocate from its relative position.
3. All areas should be addressed thoroughly and verify the necessary pay items are set up to support actions needed.

DISCLAIMER:

The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damage resulting from its use.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404--(CONTINUATION FROM EPIC SHEET 1 OF 2)

Best Management Practices for applicable Section 401 General Conditions:

Erosion

- Temporary Vegetation
- Blankets/Matting
- Mulch
- Sodding
- Interceptor Swale
- Diversion Dike
- Erosion Control Compost
- Mulch Filter Berm and Socks
- Compost Filter Berm and Socks

Sedimentation

- Silt Fence
- Rock Berm
- Triangular Filter Dike
- Sand Bag Berm
- Straw Bale Dike
- Brush Berms
- Erosion Control Compost
- Mulch Filter Berm and Socks
- Compost Filter Berm and Socks
- Stone Outlet Sediment Traps
- Sediment Basins

Post-Construction TSS

- Vegetative Filter Strips
- Retention/Irrigation Systems
- Extended Detention Basin
- Constructed Wetlands
- Wet Basin
- Erosion Control Compost
- Mulch Filter Berm and Socks
- Compost Filter Berm and Socks
- Vegetation Lined Ditches
- Sand Filter Systems

Refer also to the SW3P, project-specific EPIC sheets and Project General Notes for project specific Best Management Practices.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRD TREATY ACT (CONTINUATION FROM EPIC SHEET 1 OF 2)

Species Potentially within Project Area w/ Description

1. Texas Garter Snake: A small to medium sized terrestrial snake that can grow to about 39-48 inches long. Their backs are green to black, with a distinctive stripe of red or orange and either side features yellowish stripes.

Habitat Description

Wet or moist microhabitats are conducive to the species occurrence, but the snake is not necessarily restricted to them; hibernates underground or in or under surface cover; breeds March-August.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

*Special Note: The Migratory Bird Treaty Act of 1918 states that it is unlawful to kill, capture, collect, possess, buy, sell, trade or transport any migratory bird, nest, young, feather or egg in part or in whole, without a federal permit issued in accordance within the Act's policies and regulations. The Developer would remove all old migratory bird nests from any structures where work would be done from October 1 to February 15. In addition, the Developer would be prepared to prevent migratory birds from building nest(s) between February 15 to October 1. In the event that migratory birds are encountered on-site during project construction, effort to avoid adverse impacts on protected birds, active nests, eggs and/or young would be observed.*

LIST OF ABBREVIATIONS

- |   |   |
|---|---|
| BMP: Best Management Practice                   | SPCC: Spill Prevention Control and Countermeasure   |
| CGP: Construction General Permit                | SW3P: Storm Water Pollution Prevention Plan         |
| DSHS: Texas Department of State Health Services | PCN: Pre-Construction Notification                  |
| FHWA: Federal Highway Administration            | PSL: Project Specific Location                      |
| MOA: Memorandum of Agreement                    | TCEQ: Texas Commission on Environmental Quality     |
| MOU: Memorandum of Understanding                | TPDES: Texas Pollutant Discharge Elimination System |
| MS4: Municipal Separate Stormwater Sewer System | TPWD: Texas Parks and Wildlife Department           |
| MSDS: Material Safety Data Sheets               | TxDOT: Texas Department of Transportation           |
| MBTA: Migratory Bird Treaty Act                 | T&E: Threatened and Endangered Species              |
| NOT: Notice of Termination                      | TSS: Total Suspended Solids                         |
| NWP: Nationwide Permit                          | USACE: U.S. Army Corps of Engineers                 |
| NOI: Notice of Intent                           | USFWS: U.S. Fish and Wildlife Service               |

VII. OTHER ENVIRONMENTAL ISSUES (CONTINUATION FROM EPIC SHEET 1 OF 2)

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required       Required Action

1. Water Quality

Runoff from this project discharges within 5 stream miles of Segment 0841 of West Fork of Trinity River which is listed as threatened/impaired for PCB's, dioxins, and fecal coliform bacteria in edible tissue on the Texas 2012 303(d) list. Select appropriate BMPs to control the constituent of concern at this location.

2. MS4 Requirements

The proposed project is located within the boundaries of the Cities of Bedford, Fort Worth, Euless, Irving, and TxDOT's municipal separate storm sewer system (MS4) Phase I permits. Compliance with the applicable MS4 permit(s) is required.

3. Floodplains

Hydraulic design to be in accordance with TxDOT and FHWA design policy procedures. The proposed improvements would permit the conveyance of the design year flood, inundation of the roadway being acceptable, without causing substantial damage to the highway, stream or other property. The proposed project must not increase the base flood elevation to a level that would violate applicable floodplain regulations and ordinances.

4. Construction Air Quality

Incorporate measures to control fugitive dust during construction such as covering or treating disturbed areas with dust suppression techniques, sprinkling, covering loaded trucks and other dust abatement controls as appropriate.

5. Construction Emissions Reduction Plan

The Texas Emissions Reduction Plan (TERP) includes incentive programs to encourage the development of multi-pollutant approaches to ensure that the air in Texas is both safe to breathe and meets minimum federal standards. TxDOT encourages Developers to utilize the TERP program to the fullest extent possible to minimize diesel emissions. Information about the TERP program can be found at <http://www.tceq.state.us/implementation/air/terp/>.

6. Construction Impacts

Developer to make every reasonable effort to minimize construction noise through abatement measures such as work-hour controls (i.e., minimization of nighttime construction at residential areas) and proper maintenance of muffler systems. Notify city and local safety officials of proposed road closures or detours. Detour timing and necessary rerouting of emergency vehicles would be coordinated with the proper local officials. Lane closures and detours are to comply with TxDOT requirements and the Manual of Uniform Traffic Control Devices.

7. Visual Resources/Aesthetics

TxDOT has begun discussions with local jurisdictions regarding aesthetic features. The Developer shall adhere to the aesthetic requirements.

8. Noise


Barriers would be located opposite residences on both sides of SH 183 between Industrial Boulevard and Ector Drive (sites R-5, 6 and sites 8, 9 and 11), at a residential area on the south side of SH 183 immediately west of the Bear Creek Parkway crossing (sites R-29, 30, 31, 32, 33, 34 and 35).

GENERAL NOTE:

Any change orders and/or deviations from the final design must be reported to TxDOT prior to commencement of construction activities, as additional environmental clearance may be required.

*This document is released for information purposes and is subject to change based on comments from approving agencies and public input. It is not to be used for construction purposes*

LAST REVISION: MAY 2012

CONTROL-SECTION-JOB NUMBERS (CSJ'S)			
0364-01-054, 0364-05-025, 0364-05-925, 0094-02-077, 0094-02-977			
© 2012  Texas Department of Transportation Dallas District Standard			
ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6			SH 183 SEGMENT 2E
STATE	DIVISION	COUNTY	
TEXAS	SPD	TARRANT/DALLAS	
CONTROL	SECTION	JOB	SHEET NO.
			2 of 2

Notes To Designer:

- 1. Do not alter Sheet Design or Font style, size or weight - match text attributes.
- 2. If additional space is needed for a numbered section, fence and adjust sections up or down as needed for proportioning and readability but do not relocate from its relative position.
- 3. All areas should be addressed thoroughly and verify the necessary pay items are set up to support actions needed.

DISCLAIMER:

The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damage resulting from its use.

Revised: May 2012  
Prepared by L. Pettit of HNTB Corporation on 03/07/2014

**I. STORMWATER POLLUTION PREVENTION PLAN-CLEAN WATER ACT SECTION 402**

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 1122.

- 1. Construction General Permit (CGP) requires storm water pollution prevention plan, notice of intent, and notice of termination be prepared for the proposed improvements.

No Action Required     Required Action

Action No.

- 1. Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000.
- 2. Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- 3. Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- 4. When Developer project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

**II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404**

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas. No equipment is allowed in any stream channel below the ordinary High Water Mark except on approved temporary stream crossings or drill pads.

The Developer must adhere to all of the terms and conditions associated with the following permit(s):

No Permit Required

- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# \_\_\_\_\_

Required Actions: List Waters of the US Permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

For Proposed Improvements  
- No permanent or temporary Section 404 impacts are anticipated for the interim improvements based on the schematic.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts (or as established by the Developer).

If design changes occur to the proposed project, a reassessment of potential impacts would be necessary. If impacts to potentially jurisdictional features are identified due to the Developer's methodologies or activities, the Developer would be responsible for obtaining the appropriate Section 404 permits.

REFER TO EPIC SHEET 2 OF 2 - LEFT COLUMN  
FOR SECTION II - CONTINUATION  
FOR BEST MANAGEMENT PRACTICES

**III. CULTURAL RESOURCES**

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

No Action Required     Required Action

Action No.

- 1.
- 2.

**IV. VEGETATION RESOURCES**

Preserve native vegetation to the extent practical.

No Action Required     Required Action

Action No.

- 1. Restore and stabilize disturbed areas as soon as the construction schedule permits. Consider temporary seeding where large areas of disturbed ground would be left bare for a considerable length of time. Seeding and replanting with TxDOT approved seeding specifications that is in compliance with Executive Order 13112 shall be done where possible.

**V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS TREATY ACT.**

No Action Required     Required Action

Action No.

- 1. The Developer shall comply with all state and federal laws and regulations as related to state and federal listed threatened and endangered species. Prior to construction, the Developer shall review the most current state and federal threatened and endangered species lists to determine if changes to the lists have occurred since the applicable NEPA Approvals. If changes to the lists have occurred, the Developer shall reassess the potential project impacts to the listed species and/or their habitat. The Developer shall take all appropriate actions to comply with applicable state and federal regulations. If it is determined that adverse effects to listed species will occur, the Developer shall work with TxDOT to develop mitigation approaches. The Developer shall prepare any materials needed for coordination or consultation with regulatory agencies, at TxDOT's direction. TxDOT will conduct coordination or consultation with the applicable state and federal agencies for the project. The Developer shall implement the required actions established from regulatory agency coordination/consultation that are necessary to satisfy TxDOT's mitigation obligation.
- 2. Between October 1 and February 15, remove all old migratory bird nests from any structures that would be affected by the proposed project, and complete any bridge work and/or vegetation clearing. Between February 15 and October 1, the Developer would be prepared to prevent migratory birds from building nests. In the event that migratory birds are encountered on-site during project construction, adverse impacts on protected birds, active nests, eggs and/or young would be avoided. If species are present, work should cease at that location and TxDOT personnel should be contacted. If any active nests are found, the local USFWS biologist should be contacted by TxDOT to determine an appropriate plan of action.

REFER TO EPIC SHEET 2 OF 2 - MIDDLE COLUMN  
FOR SECTION V - CONTINUATION  
FOR LIST OF SPECIES POTENTIALLY WITHIN PROJECT AREA  
WITH HABITAT DESCRIPTION AND ADDITIONAL ACTIONS

**LIST OF ABBREVIATIONS**

BMP: Best Management Practice	STA: Stations
CDC: Corridor Development Certificate	PCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
CSN: Construction Site Notice	PCN: Pre-Construction Notification
DSHS: Texas Department of State Health Services	PSL: Project Specific Location
EPA: Environmental Protection Agency	TCEQ: Texas Commission on Environmental Quality
FHWA: Federal Highway Administration	TERP: Texas Emissions Reduction Plan
ML: Mainlines	TPDES: Texas Pollutant Discharge Elimination System
MOA: Memorandum of Agreement	TPWD: Texas Parks and Wildlife Department
MOU: Memorandum of Understanding	TSS: Total Suspended Solids
MS4: Municipal Separate Stormwater Sewer System	TxDOT: Texas Department of Transportation
NEPA: National Environmental Policy Act	T&E: Threatened and Endangered Species
NOT: Notice of Termination	USACE: U.S. Army Corp of Engineers
NWP: Nationwide Permit	USFWS: U.S. Fish and Wildlife Service
NOI: Notice of Intent	

**VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES**

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labeling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Developer shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer and Developer's Environmental Compliance Manager if any of the following are detected:

- \* Dead or distressed vegetation (not identified as normal)
- \* Trash piles, drums, canisters, barrels, etc.
- \* Undesirable smells or odors
- \* Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation(s) or replacement(s) (bridge class structures not including box culverts)?

Yes     No

If "No", then no further action is required.

If "Yes", then the Developer is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

Yes     No

If "Yes", then the Developer must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then the Developer is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Developer is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Developer and the asbestos consultant.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

No Action Required     Required Action

Action No.

- 1. The Developer shall comply with the recommendations of the limited Phase 1 environmental site assessment completed for the SH 183 Managed Lanes Project.

- 2. Any unanticipated hazardous materials encountered during construction would be handled according to applicable federal, state, and local regulations per the Contract Documents. The Developer would take appropriate measures to prevent, minimize, and control the spill of hazardous materials in the construction staging area. All construction materials used for this project would be removed as soon as the work schedules permit.

**VII. OTHER ENVIRONMENTAL ISSUES**

(includes regional issues such as Edwards Aquifer District, etc.)

REFER TO EPIC SHEET 2 OF 2 - RIGHT COLUMN  
FOR SECTION VII - CONTINUATION  
FOR OTHER ENVIRONMENTAL ISSUES

**PREPARED FOR INTERIM IMPROVEMENTS**

CONTROL-SECTION-JOB NUMBERS (CSJ's)  
0581-02-077, 0581-02-128, 0581-02-911,  
0094-03-116, 0094-03-976, 0581-02-124,  
0094-03-060, 0196-03-137

© 2014 Texas Department of Transportation  
Dallas District Standard

**ENVIRONMENTAL PERMITS,  
ISSUES AND COMMITMENTS  
(EPIC)** SHEET 1 OF 2

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	SEE TITLE SHEET	LP 12
STATE	DISTRICT	COUNTY
TEXAS	DALLAS	DALLAS
CONTROL	SECTION	JOB
0581	02	077, etc.
		SHEET NO.

This document is released for informational purposes and is subject to change based on comments from approving agencies and public input. It is not to be used for construction purposes.

LAST REVISION: MAY 2012

Notes To Designer:

1. Do not alter Sheet Design or Font style, size or weight - match text attributes.
2. If additional space is needed for a numbered section, fence and adjust sections up or down as needed for proportioning and readability but do not relocate from its relative position.
3. All areas should be addressed thoroughly and verify the necessary pay items are set up to support actions needed.

DISCLAIMER:

The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damage resulting from its use.

Revised: May 2012  
Prepared by L. Pettit of HNTB Corporation on 03/07/2014

**II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404-- (CONTINUATION FROM EPIC SHEET 1 OF 2)**

Best Management Practices for applicable Section 401 General Conditions:

- |  |  |  |
|--|--|--|
| <b>Erosion</b>   | <b>Sedimentation</b>                                   | <b>Post-Construction TSS</b>                                 |
| <input checked="" type="checkbox"/> Temporary Vegetation | <input checked="" type="checkbox"/> Silt Fence         | <input type="checkbox"/> Vegetative Filter Strips            |
| <input type="checkbox"/> Blankets/Matting                | <input checked="" type="checkbox"/> Rock Berm          | <input type="checkbox"/> Retention/Irrigation Systems        |
| <input checked="" type="checkbox"/> Mulch                | <input type="checkbox"/> Triangular Filter Dike        | <input type="checkbox"/> Extended Detention Basin            |
| <input checked="" type="checkbox"/> Sodding              | <input type="checkbox"/> Sand Bag Berm                 | <input type="checkbox"/> Constructed Wetlands                |
| <input type="checkbox"/> Interceptor Swale               | <input type="checkbox"/> Straw Bale Dike               | <input type="checkbox"/> Wet Basin                           |
| <input type="checkbox"/> Diversion Dike                  | <input type="checkbox"/> Brush Berms                   | <input type="checkbox"/> Erosion Control Compost             |
| <input type="checkbox"/> Erosion Control Compost         | <input type="checkbox"/> Erosion Control Compost       | <input type="checkbox"/> Mulch Filter Berm and Socks         |
| <input type="checkbox"/> Mulch Filter Berm and Socks     | <input type="checkbox"/> Mulch Filter Berm and Socks   | <input type="checkbox"/> Compost Filter Berm and Socks       |
| <input type="checkbox"/> Compost Filter Berm and Socks   | <input type="checkbox"/> Compost Filter Berm and Socks | <input checked="" type="checkbox"/> Vegetation Lined Ditches |
|  | <input type="checkbox"/> Stone Outlet Sediment Traps   | <input type="checkbox"/> Sand Filter Systems                 |
|  | <input type="checkbox"/> Sediment Basins               |  |

Refer also to the SW3P and Project General Notes for project specific Best Management Practices.

**V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS TREATY ACT. (CONTINUATION FROM EPIC SHEET 1 OF 2)**

Species Potentially within Project Area w/ Description	Habitat Description
1. Cave Myotis Bat: Relatively larger than typical Myotis. It can be distinguished by the presence of a conspicuous bare patch on its back. Its color is brown and it has short ears.	Cave-dwelling; also roosts in old buildings and under bridges; roosts in clusters of up to thousands of individuals; hibernates during winter, opportunistic insectivore.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediated area, and contact the Engineer immediately.

*Special Note: The Migratory Bird Act of 1918 states that it is unlawful to kill, capture, collect, possess, buy, sell, trade or transport any migratory bird, nest, young, feather or egg in part or in whole, without a federal permit issued in accordance within the Act's policies and regulations. The Developer would remove all old migratory bird nests from any structure where work would be done from October 1 to February 15. In addition, the Developer would be prepared to prevent migratory birds from building nest(s) between February 15 to October 1. In the event that migratory birds are encountered on-site during project construction, efforts to avoid adverse impacts on protected birds, active nests, eggs and/or young would be observed.*

**LIST OF ABBREVIATIONS**

BMP: Best Management Practice	STA: Stations
CDC: Corridor Development Certificate	PCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
CSN: Construction Site Notice	PCN: Pre-Construction Notification
DSHS: Texas Department of State Health Services	PSL: Project Specific Location
EPA: Environmental Protection Agency	TCEQ: Texas Commission on Environmental Quality
FHWA: Federal Highway Administration	TERP: Texas Emissions Reduction Plan
ML: Mainlanes	TPDES: Texas Pollutant Discharge Elimination System
MOA: Memorandum of Agreement	TPWD: Texas Parks and Wildlife Department
MOU: Memorandum of Understanding	TSS: Total Suspended Solids
MS4: Municipal Separate Stormwater Sewer System	TxDOT: Texas Department of Transportation
NEPA: National Environmental Policy Act	T&E: Threatened and Endangered Species
NOT: Notice of Termination	USACE: U.S. Army Corp of Engineers
NWP: Nationwide Permit	USFWS: U.S. Fish and Wildlife Service
NOI: Notice of Intent	

**VII. OTHER ENVIRONMENTAL ISSUES (CONTINUATION FROM EPIC SHEET 1 OF 2)**

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required       Required Action

Action No.	
1. Water Quality	Runoff from this project discharges within 5 stream miles upstream of Segment 0802 of Upper Trinity River which is listed as threatened/impaired for PCB's and dioxins in edible tissue on the Texas 2012 303(d) list. Select appropriate BMP's to control the constituent of concern at this location.
2. MS4 Requirements	The proposed project is located within the boundaries of the Cities of Irving and Dallas and TxDOT's municipal separate storm sewer system (MS4) Phase I permits. Compliance with the applicable MS4 permit(s) is required.
3. Trinity River Corridor	Portions of the project cross the Trinity River Corridor; therefore a Corridor Development Certificate (CDC) is required. The Developer is responsible to coordinate and obtain the CDC.
4. Floodplains	Hydraulic design to be in accordance with TxDOT and FHWA design policy procedures. The proposed improvements would permit the conveyance of the design year flood, inundation of the roadway being acceptable, without causing substantial damage to the highway, stream or other property. The proposed project must not increase the base flood elevation to a level that would violate applicable floodplain regulations and ordinances. There is no change in commitment since the 2009 EA.
5. Construction Air Quality	Incorporate measures to control fugitive dust during construction such as covering or treating disturbed areas with dust suppression techniques, sprinkling, covering loaded trucks and other dust abatement controls as appropriate.
6. Construction Emissions Reduction Plan	The Texas Emissions Reduction Plan (TERP) includes incentive programs to encourage the development of multi-pollutant approaches to ensure that the air in Texas is both safe to breathe and meets minimum federal standards. TxDOT encourages Developers to utilize the TERP program to the fullest extent possible to minimize diesel emissions. Information about the TERP program can be found at <a href="http://www.tceq.state.us/implementation/air/terp/">http://www.tceq.state.us/implementation/air/terp/</a> .
7. Construction Impacts	Developer to make every reasonable effort to minimize construction noise through abatement measures such as work-hour controls (i.e., minimization of nighttime construction at residential areas) and proper maintenance of muffler systems. Notify city and local safety officials of proposed road closures or detours. Detour timing and necessary rerouting of emergency vehicles would be coordinated with the proper local officials. Lane closures and detours are to comply with TxDOT requirements and the Manual of Uniform Traffic Control Devices.
8. Visual Resources/Aesthetics	TxDOT has begun discussions with local jurisdictions regarding aesthetic features and anticipates that the Developer will adhere to these aesthetic requirements.

**GENERAL NOTE:**

Any change orders and/or deviations from the final design must be reported to the Engineer prior to commencement of construction activities, as additional environmental clearance may be required.

*This document is released for informational purposes and is subject to change based on comments from approving agencies and public input. It is not to be used for construction purposes.*

LAST REVISION: MAY 2012

**PREPARED FOR INTERIM IMPROVEMENTS**

CONTROL-SECTION-JOB NUMBERS (CSJ's)
0581-02-077, 0581-02-128, 0581-02-911, 0094-03-116, 0094-03-976, 0581-02-124, 0094-03-060, 0196-03-137

© 2014 Texas Department of Transportation  
Dallas District Standard

**ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)** SHEET 2 OF 2

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	SEE TITLE SHEET	LP 12
STATE	DISTRICT	COUNTY
TEXAS	DALLAS	DALLAS
CONTROL	SECTION	JOB
0581	02	077, etc.
		SHEET NO.

Notes To Designer: 1. Do not alter Sheet Design or Font style, size or weight - match text attributes. 2. If additional space is needed for a numbered section, fence and adjust sections up or down as needed for proportioning and readability but do not relocate from its relative position. 3. All areas should be addressed thoroughly and verify the necessary pay items are set up to support actions needed. Revised: May 2012 Prepared by L. Pettit of HNTB Corporation on 03/07/2014  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damage resulting from its use.

**I. STORMWATER POLLUTION PREVENTION PLAN-CLEAN WATER ACT SECTION 402**

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 1122.

- 1. Construction General Permit (CGP) requires storm water pollution prevention plan, notice of intent, and notice of termination be prepared for the proposed improvements.

No Action Required     Required Action

Action No.

- 1. Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000.
- 2. Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- 3. Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- 4. When Developer project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

**II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404**

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas. No equipment is allowed in any stream channel below the ordinary High Water Mark except on approved temporary stream crossings or drill pads.

The Developer must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# \_\_\_\_\_

Required Actions: List Waters of the US Permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

Permit	Waters of the US	Approx location	ML STA
NWP 14	Site 3	Tributary to Grapevine Creek	SH 114 STA 599+00
NWP 14	Site 8	South Fork Creek	SH 114 STA 775+00 TO 781+00
NWP 14	Site 9	Tributary to Hackberry Creek	SH 114 STA 839+50
NWP 14	Site 10	Cottonwood Branch	SH 114 STA 860+50 TO 862+00

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts (or as established by the Developer).

If design changes occur to the proposed project, a reassessment of potential impacts would be necessary. If impacts to potentially jurisdictional features are identified due to the Developer's methodologies or activities, the Developer would be responsible for obtaining the appropriate Section 404 permits.

REFER TO EPIC SHEET 2 OF 2 - LEFT COLUMN FOR SECTION II - CONTINUATION FOR BEST MANAGEMENT PRACTICES

**III. CULTURAL RESOURCES**

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

No Action Required     Required Action

Action No.

- 1.
- 2.

**IV. VEGETATION RESOURCES**

Preserve native vegetation to the extent practical.

No Action Required     Required Action

Action No.

- 1. Restore and stabilize disturbed areas as soon as the construction schedule permits. Consider temporary seeding where large areas of disturbed ground would be left bare for a considerable length of time. Seeding and replanting with TxDOT approved seeding specifications that is in compliance with Executive Order 13112 shall be done where possible.

**V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS TREATY ACT.**

No Action Required     Required Action

Action No.

- 1. The Developer shall comply with all state and federal laws and regulations as related to state and federal listed threatened and endangered species. Prior to construction, the Developer shall review the most current state and federal threatened and endangered species lists to determine if changes to the lists have occurred since the applicable NEPA Approvals. If changes to the lists have occurred, the Developer shall reassess the potential project impacts to the listed species and/or their habitat. The Developer shall take all appropriate actions to comply with applicable state and federal regulations. If it is determined that adverse effects to listed species will occur, the Developer shall work with TxDOT to develop mitigation approaches. The Developer shall prepare any materials needed for coordination or consultation with regulatory agencies, at TxDOT's direction. TxDOT will conduct coordination or consultation with the applicable state and federal agencies for the project. The Developer shall implement the required actions established from regulatory agency coordination/consultation that are necessary to satisfy TxDOT's mitigation obligation.
- 2. Between October 1 and February 15, remove all old migratory bird nests from any structures that would be affected by the proposed project, and complete any bridge work and/or vegetation clearing. Between February 15 and October 1, the Developer would be prepared to prevent migratory birds from building nests. In the event that migratory birds are encountered on-site during project construction, adverse impacts on protected birds, active nests, eggs and/or young would be avoided. If species are present, work should cease at that location and TxDOT personnel should be contacted. If any active nests are found, the local USFWS biologist should be contacted by TxDOT to determine an appropriate plan of action.

REFER TO EPIC SHEET 2 OF 2 - MIDDLE COLUMN FOR SECTION V - CONTINUATION FOR LIST OF SPECIES POTENTIALLY WITHIN PROJECT AREA WITH HABITAT DESCRIPTION AND ADDITIONAL ACTIONS

LIST OF ABBREVIATIONS	
BMP: Best Management Practice	STA: Stations
CDC: Corridor Development Certificate	PCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
CSN: Construction Site Notice	PCN: Pre-Construction Notification
DSHS: Texas Department of State Health Services	PSL: Project Specific Location
EPA: Environmental Protection Agency	TCEQ: Texas Commission on Environmental Quality
FHWA: Federal Highway Administration	TERP: Texas Emissions Reduction Plan
ML: Mainlines	TPDES: Texas Pollutant Discharge Elimination System
MOA: Memorandum of Agreement	TPWD: Texas Parks and Wildlife Department
MOU: Memorandum of Understanding	TSS: Total Suspended Solids
MS4: Municipal Separate Stormwater Sewer System	TxDOT: Texas Department of Transportation
NEPA: National Environmental Policy Act	T&E: Threatened and Endangered Species
NOT: Notice of Termination	USACE: U.S. Army Corp of Engineers
NWP: Nationwide Permit	USFWS: U.S. Fish and Wildlife Service
NOI: Notice of Intent	

**VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES**

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labeling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Developer shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer and Developer's Environmental Compliance Manager if any of the following are detected:

- \* Dead or distressed vegetation (not identified as normal)
- \* Trash piles, drums, canisters, barrels, etc.
- \* Undesirable smells or odors
- \* Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation(s) or replacement(s) (bridge class structures not including box culverts)?

Yes     No

If "No", then no further action is required.

If "Yes", then the Developer is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

Yes     No

If "Yes", then the Developer must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then the Developer is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Developer is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Developer and the asbestos consultant.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

No Action Required     Required Action

Action No.

- 1. The Developer shall comply with the recommendations of the limited Phase 1 environmental site assessment completed for the SH 183 Managed Lanes Project.

- 2. Any unanticipated hazardous materials encountered during construction would be handled according to applicable federal, state, and local regulations per the Contract Documents. The Developer would take appropriate measures to prevent, minimize, and control the spill of hazardous materials in the construction staging area. All construction materials used for this project would be removed as soon as the work schedules permit.

**VII. OTHER ENVIRONMENTAL ISSUES**

(includes regional issues such as Edwards Aquifer District, etc.)

REFER TO EPIC SHEET 2 OF 2 - RIGHT COLUMN FOR SECTION VII - CONTINUATION FOR OTHER ENVIRONMENTAL ISSUES

**GENERAL NOTE:**

Any change orders and/or deviations from the final design must be reported to the Engineer prior to commencement of construction activities, as additional environmental clearance may be required.

This document is released for informational purposes and is subject to change based on comments from approving agencies and public input. It is not to be used for construction purposes.

CONTROL-SECTION-JOB NUMBERS (CSJ's)			
0353-04-056, 0353-04-907, 0353-06-025, 0353-06-905, 0353-06-054, 0353-06-906, 0581-02-128, and 0581-02-911 (former 0581-02-121)			
© 2014 Texas Department of Transportation Dallas District Standard			
ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)			
SHEET 1 OF 2			
FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
6	SEE TITLE SHEET		SH 114
STATE	DISTRICT	COUNTY	
TEXAS	DALLAS	DALLAS	
CONTROL	SECTION	JOB	SHEET NO.
0353	04	056, etc.	

LAST REVISION: MAY 2012



Notes To Designer:

1. Do not alter Sheet Design or Font style, size or weight - match text attributes.
2. If additional space is needed for a numbered section, fence and adjust sections up or down as needed for proportioning and readability but do not relocate from its relative position.
3. All areas should be addressed thoroughly and verify the necessary pay items are set up to support actions needed.

DISCLAIMER:

The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damage resulting from its use.

Revised: May 2012  
Prepared by L. Pettit of HNTB Corporation on 03/07/2014

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404-- (CONTINUATION FROM EPIC SHEET 1 OF 2)

Best Management Practices for applicable Section 401 General Conditions:

- |  |  |  |
|--|--|--|
| <b>Erosion</b>   | <b>Sedimentation</b>                                   | <b>Post-Construction TSS</b>                                 |
| <input checked="" type="checkbox"/> Temporary Vegetation | <input checked="" type="checkbox"/> Silt Fence         | <input type="checkbox"/> Vegetative Filter Strips            |
| <input type="checkbox"/> Blankets/Matting                | <input checked="" type="checkbox"/> Rock Berm          | <input type="checkbox"/> Retention/Irrigation Systems        |
| <input checked="" type="checkbox"/> Mulch                | <input type="checkbox"/> Triangular Filter Dike        | <input type="checkbox"/> Extended Detention Basin            |
| <input checked="" type="checkbox"/> Sodding              | <input type="checkbox"/> Sand Bag Berm                 | <input type="checkbox"/> Constructed Wetlands                |
| <input type="checkbox"/> Interceptor Swale               | <input type="checkbox"/> Straw Bale Dike               | <input type="checkbox"/> Wet Basin                           |
| <input type="checkbox"/> Diversion Dike                  | <input type="checkbox"/> Brush Berms                   | <input type="checkbox"/> Erosion Control Compost             |
| <input type="checkbox"/> Erosion Control Compost         | <input type="checkbox"/> Erosion Control Compost       | <input type="checkbox"/> Mulch Filter Berm and Socks         |
| <input type="checkbox"/> Mulch Filter Berm and Socks     | <input type="checkbox"/> Mulch Filter Berm and Socks   | <input type="checkbox"/> Compost Filter Berm and Socks       |
| <input type="checkbox"/> Compost Filter Berm and Socks   | <input type="checkbox"/> Compost Filter Berm and Socks | <input checked="" type="checkbox"/> Vegetation Lined Ditches |
|  | <input type="checkbox"/> Stone Outlet Sediment Traps   | <input type="checkbox"/> Sand Filter Systems                 |
|  | <input type="checkbox"/> Sediment Basins               |  |

Refer also to the SW3P and Project General Notes for project specific Best Management Practices.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS TREATY ACT. (CONTINUATION FROM EPIC SHEET 1 OF 2)

Species Potentially within Project Area w/ Description	Habitat Description
1. Henslow's Sparrow: Adults have streaked brown upperparts with a light brown breast with streaks, a white belly and a white throat. Have a pale stripe on the crown with a dark stripe on each side, an olive face and neck, rust-colored wings and short dark forked tail.	Wintering individuals (not flocks) found in weedy fields or cut-over areas where lots of bunch grasses occur along with vines and brambles; a key component is bare ground for running/walking.
2. Western Burrowing Owl: Distinctive long legs, a short tail, and very serious-looking eyes. Lacks ear tufts. Feathers are sandy brown color above, white breast area is beige with spotted bars.	Open grasslands, especially prairie, plains, and savanna, sometimes in open areas such as vacant lots near human habitation or airports; nests and roosts in abandoned burrows.
3. Cave Myotis Bat: Relatively larger than typical Myotis. It can be distinguished by the presence of a conspicuous bare patch on its back. Its color is brown and it has short ears.	Cave-dwelling; also roosts in old buildings and under bridges; roosts in clusters of up to thousands of individuals; hibernates during winter, opportunistic insectivore.
4. Plains Spotted Skunk: Small, slender mammal with short legs and black tail with prominent, long hairs. Skunk is black overall with narrow, white stripes and spots. Four stripes on the neck, back and sides run from the head to the middle of body. There is a white spot on the forehead and in front of each ear.	Catholic; open fields, prairies, croplands, fence rows, farmyards, forest edges, and woodlands; prefers wooded, brushy areas and tallgrass prairie.
5. Mussels (Fawnsfoot, Little Spectaclecase, Louisiana pigtoe, Texas heelsplitter, Wabash pigtoe): Adult can range from approximately 1-inch to 12-inches in length. Some species have thin shells and shells vary both on the inside and outside of mussels, depending on species. Color, texture and shape variations in shells are used to help identify types of mussels.	Small and large rivers especially on sand, mud, rocky mud and sand and gravel, also still to swiftly flowing waters.
6. Texas Garter Snake: A small to medium sized terrestrial snake that can grow to about 39-48 inches long. Their backs are green to black, with a distinctive stripe of red or orange and either side features yellowish stripes.	Wet or moist microhabitats are conducive to the species occurrence, but the snake is not necessarily restricted to them; hibernates underground or in or under surface cover; breeds March-August

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediated area, and contact the Engineer immediately.

*Special Note: The Migratory Bird Act of 1918 states that it is unlawful to kill, capture, collect, possess, buy, sell, trade or transport any migratory bird, nest, young, feather or egg in part or in whole, without a federal permit issued in accordance within the Act's policies and regulations. The Developer would remove all old migratory bird nests from any structure where work would be done from October 1 to February 15. In addition, the Developer would be prepared to prevent migratory birds from building nest(s) between February 15 to October 1. In the event that migratory birds are encountered on-site during project construction, efforts to avoid adverse impacts on protected birds, active nests, eggs and/or young would be observed.*

LIST OF ABBREVIATIONS

BMP: Best Management Practice	STA: Stations
CDC: Corridor Development Certificate	PCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
CSN: Construction Site Notice	PCN: Pre-Construction Notification
DSHS: Texas Department of State Health Services	PSL: Project Specific Location
EPA: Environmental Protection Agency	TCEQ: Texas Commission on Environmental Quality
FHWA: Federal Highway Administration	TERP: Texas Emissions Reduction Plan
ML: Mainlanes	TPDES: Texas Pollutant Discharge Elimination System
MOA: Memorandum of Agreement	TPWD: Texas Parks and Wildlife Department
MOU: Memorandum of Understanding	TSS: Total Suspended Solids
MS4: Municipal Separate Stormwater Sewer System	TxDOT: Texas Department of Transportation
NEPA: National Environmental Policy Act	T&E: Threatened and Endangered Species
NOT: Notice of Termination	USACE: U.S. Army Corp of Engineers
NWP: Nationwide Permit	USFWS: U.S. Fish and Wildlife Service
NOI: Notice of Intent	

VII. OTHER ENVIRONMENTAL ISSUES (CONTINUATION FROM EPIC SHEET 1 OF 2)

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required       Required Action

Action No.	
1. Water Quality	Runoff from this project discharges within 5 stream miles upstream of Segment 0802 of Upper Trinity River which is listed as threatened/impaired for PCB's and dioxins in edible tissue on the Texas 2012 303(d) list. Select appropriate BMP's to control the constituent of concern at this location.
2. MS4 Requirements	The proposed project is located within the boundaries of the Cities of Irving and Dallas and TxDOT's municipal separate storm sewer system (MS4) Phase I permits. Compliance with the applicable MS4 permit(s) is required.
3. Trinity River Corridor	Portions of the project cross the Trinity River Corridor; therefore a Corridor Development Certificate (CDC) is required. The Developer is responsible to coordinate and obtain the CDC.
4. Floodplains	Hydraulic design to be in accordance with TxDOT and FHWA design policy procedures. The proposed improvements would permit the conveyance of the design year flood, inundation of the roadway being acceptable, without causing substantial damage to the highway, stream or other property. The proposed project must not increase the base flood elevation to a level that would violate applicable floodplain regulations and ordinances. There is no change in commitment since the 2009 EA.
5. Construction Air Quality	Incorporate measures to control fugitive dust during construction such as covering or treating disturbed areas with dust suppression techniques, sprinkling, covering loaded trucks and other dust abatement controls as appropriate.
6. Construction Emissions Reduction Plan	The Texas Emissions Reduction Plan (TERP) includes incentive programs to encourage the development of multi-pollutant approaches to ensure that the air in Texas is both safe to breathe and meets minimum federal standards. TxDOT encourages Developers to utilize the TERP program to the fullest extent possible to minimize diesel emissions. Information about the TERP program can be found at <a href="http://www.tceq.state.us/implementation/air/terp/">http://www.tceq.state.us/implementation/air/terp/</a> .
7. Construction Impacts	Developer to make every reasonable effort to minimize construction noise through abatement measures such as work-hour controls (i.e., minimization of nighttime construction at residential areas) and proper maintenance of muffler systems. Notify city and local safety officials of proposed road closures or detours. Detour timing and necessary rerouting of emergency vehicles would be coordinated with the proper local officials. Lane closures and detours are to comply with TxDOT requirements and the Manual of Uniform Traffic Control Devices.
8. Visual Resources/Aesthetics	TxDOT has begun discussions with local jurisdictions regarding aesthetic features and anticipates that the Developer will adhere to these aesthetic requirements.

GENERAL NOTE:

Any change orders and/or deviations from the final design must be reported to the Engineer prior to commencement of construction activities, as additional environmental clearance may be required.

*This document is released for informational purposes and is subject to change based on comments from approving agencies and public input. It is not to be used for construction purposes.*

CONTROL-SECTION-JOB NUMBERS (CSJ's)  
0353-04-056, 0353-04-907, 0353-06-025, 0353-06-905, 0353-06-054, 0353-06-906, 0581-02-128, and 0581-02-911 (former 0581-02-121)

© 2014 Texas Department of Transportation  
Dallas District Standard

ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC) SHEET 2 OF 2

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
6	SEE TITLE SHEET	SH 114
STATE	DISTRICT	COUNTY
TEXAS	DALLAS	DALLAS
CONTROL	SECTION	JOB
0353	04	056, etc.
		SHEET NO.

LAST REVISION: MAY 2012